S-115 Academy Grove Historic District Upper Fairmount vicinity annual public fair c. 1860-1872

The Academy Grove Historic District comprises two well-known frame buildings, the Fairmount Academy and the Knights of Pythias Hall. Located between Upper and Lower Fairmount, these two Italianate-influenced structures are enhanced by a setting of a mature grove of cedar, oak and pine. Notable features which tie both buildings together architecturally include the bracketed eaves and corner pilasters. In addition to its architectural significance, the district is important for its association with the development of public education and civic organizations in the county during the second half of the nineteenth century.

Local tradition refers to an 1839 date of establishment for a school on "Potato Neck." The earliest documented reference is found in the will of Lazarus Maddox, proved on March 26, 1841,

It is my will that I now establish and confirm the following to be the line between my home farm above described and my other lands hereafter mentioned—commencing at the north—west corner of my field adjoining Edward T. Hall's store on the north side of the county road in Potato Neck, from thence running with a straight line to a marked pine tree standing near the School House down the neck on the same side of the County road aforesaid.(JP5/117)

This marked pine and school house are referred to in an 1848 plat of a nineteeen and three-eighth's acre parcel of Daniel Ballard's land, known as "School House Ridge." With these two firm references, it appears that a school was located on or near this site as early as 1839. However, a proper deed had not been executed for the school house ground. In 1867, Thomas Emery Ballard granted




In 1888, the Fairmount Academy building was graced with a school bell credered through the McShane Bell Foundry, McShane Company of Baltimore, Maryland, and probably delivered by steamboat. From the late nineteenth century until 1927, all twelve grades were offered by an academy staff of five; one principal and four teachers. Beginning in 1927, the grades were cut back to one through seven, and from 1944 to 1969 only the first six grades were taught.

In 1972 a decision to auction off all unused school building was made by the Somerset County Commissioners. This action galvanized a group of local residents to establish the Fairmount Academy Historical Association. This group maintains the two buildings and holds an annual fair in the spring.

United States Department of the Interior Heritage Conservation and Recreation Service

### **National Register of Historic Places Inventory—Nomination Form**

See instructions in How to Complete National Register Forms



Type all e	ntries—complete ap	plicable sec	tions			
1. N	ame					
historic	Fairmou	nt Academy	/ (Potato Neck Sc	hool) and Knights o	f Pythias H	lall
and/or com			storic District	(preferred)		
2. Lo	ocation		Jeorie District	(preferred)		<del>-</del>
street & nu	mber North s	ide of Mar	yland Route 361(	Carrison - Kombi, kop	Za not for pub	* 9/3/9 -
city, town		airmount	_X vicinity of	congressional district	First	
state	Maryland	d code	24 county	Somerset	code	039
3. CI	assificati	on				
Category  districtX buildin structu site object	g(s) X private	ition #	Status  X occupied  unoccupied  work in progress  ccessible  yes: restricted  no	Present Use agriculture commercial educational entertainment government industrial military	X museun park private i religious scientifi transpoi	residence s ic
4. O	wner of Pr	operty	<i>y</i>			
name	Fairmoun	t Academy	Historical Assoc	ciation		
street & nun	nber c/o Neve	tte Muir				
city, town	Upper Fa	irmount	n/a vicinity of	state	Maryland	21867
5. Lo	cation of	Legal	Description	on		
courthouse,	registry of deeds, etc.	Clerk of	Court		¥	
street & nun	nber	Somerset	County Courthou	se		
ity, town		Princess	s Anne	state	Maryland	21853
6. Re	presentat	ion in	Existing S			
Man	ryland Historica storic Sites Inv	1 Trust		perty been determined eleg	jible? ye:	s _X_ no
late 198	33			federal X_ state	county	local
lepository fo	or survey records	Maryland	Historical Trus	t, 21 State Circle		
ity town		Annapoli		*	Maruland	21/01

7. Description	. Description 6 s-115				
Condition  X excellent deteriorat  good ruins  fair unexpose	X altered	Check one  X original site moved date n/a			
Describe the present and orig	inal (if known) phys	sical appearance	<del></del>		
Number of Resources	<b>;</b>	Number of previously listed			
Contributing No	ncontributing 0 buildings 0 sites	National Register properties included in this nomination:	0		

\_structures objects

0 Total

2

Original and historic functions

and uses: educational, civic

The Academy Grove Historic District comprises two Italianate-influenced frame buildings located in a grove of trees on the northwest side of Maryland Route 361 east of the village of Fairmount in Somerset County, Maryland. The two buildings include the Fairmount Academy, constructed c. 1860-67 to serve as a public school for the Potato Neck District, and the Knights of Pythias Hall, erected adjacent to the Academy c. 1872 by the Fairmount Lodge No. 77 of the Knights of Pythias. The two buildings are similar in form, construction, and detailing. Both are rectangular frame structures, two stories high, with symmetrical three-bay principal facades facing southeast. Entrances feature double-leaf doors in transomed Classical surrounds. The buildings are sheathed in weatherboard, and feature bracketed cornices and narrow paneled pilasters at their corners. The Knights of Pythias Hall is gable-roofed, while the Academy has a hipped roof to which an open belfry was added in 1888. Interior plan and appointments are likewise similar, with a vestibule and stair hall across the front, opening into a large open class or meeting room on each floor. buildings served a common educational function as early as 1883, when the Knights of Pythias Hall was rented by the Board of Education; when the Fairmount Lodge disbanded in 1911, the Hall continued to provide additional classroom space for the Academy.

OMB No. 1024-0018 Exp. 10-31-84

S-115

# United States Department of the Interior National Park Service

## National Register of Historic Places Inventory—Nomination Form

For NFS use only received date entered

Academy Grove Historic District

Continuation sheet Somerset County, Maryland Item number

Page

1

### GENERAL DESCRIPTION:

The two buildings comprising the Academy Grove Historic District are described briefly below:

Fairmount Academy (S-108)

Fairmount Academy is located between Upper Fairmount and Fairmount on the northwest side of Maryland 361. The frame school building faces southeast with the axis of the roof running in a northwest/southeast direction.

The c. 1860-1867 two-story rectangular frame Italianate structure is supported by a minimal brick foundation and covered by a steeply pitched asphalt tile hip roof. The building measures 30'7" by 45'7" and is uniformly sheathed with weatherboard siding. A small frame bell tower is centered on the roof.

The southeast facade is three bays across with center double doors flanked by 12/12 sash windows. The double doors are replacements but the four-light transom and dentiled lintel are original features. Three 12/12 sash windows pierce the second floor. The four corners of the building are trimmed with paneled pilasters, and the eaves are distinguished with brackets.

Both side walls are pierced by an asymmetrical arrangement of 12/12 sash which light the main rooms on both floors. A side entrance into the front hall and an interior brick stove stack are on the southwest elevation.

The rear facade has four boarded windows, two on each floor, along with a back door.

Inside both the first and second floors are divided into two rooms; a small stair hall or vestibule in front and the large classroom behind. On the main floor twin stairs flank the entrance and rise opposite each other to the second floor. A heavily turned newel post and tapered oak balusters support an oval profile handrail. Under each stair a small room has been partitioned for a bathroom on the right and storage on the left. Two door openings pierce the vestibule partition and open into the first floor classroom. A centrally located, fluted iron post supports the floor above. Blackboards are fixed to the side and back walls.

The second floor is divided in the same manner. However, a stage has been added to the large classroom. Standing on the stage is a platform with the school bell inscribed by McShane Bell Foundry, Henry McShane and Company, Baltimore, MD., 1888. The front room was mainly used for storage but does contain a ladder for access onto the roof.

OMB No 1024-0018 Exp 10-31-84

S-115

# United States Department of the Interior National Park Service

### National Register of Historic Places Inventory—Nomination Form

Academy Grove Historic District

Continuation sheet Somerset County, Maryland Item number

For NPS use only received date entered

7

Page

2

GENERAL DESCRIPTION (continued)

Knights of Pythias Hall (5-109)

The Knights of Pythias Hall is located next to Fairmount Academy between Upper and Lower Fairmount on the northwest side of Maryland 361. The frame building faces southeast with the axis of the gable roof running in a northwest/southeast direction.

The c. 1872-1875 two-story three bay by two room weatherboard frame structure is supported by a minimal brick foundation and is covered by a medium sloped asphalt tile roof. The eaves are extended as well as bracketed. Like the adjacent Fairmount Academy, the building is trimmed on each corner with paneled pilasters.

The southeast facade is three bays across with center double doors and flanking 6/6 sash windows. The double doors are replacements, but the simple classical surround, dentiled cornice and two-light transom are original features. Two 6/6 sash windows light the second floor, and one 6/6 sash window lights the attic.

Each side is three bays across. The southwest facade has three 6/6 sash on each floor, while the northeast side has a side entrance that is flanked by 6/6 sash windows. Like the Academy building, the rear windows have been boarded over. A brick stove stack rises out of the center of the building against the interior partition.

The plan of this building is similar to the Academy. The main difference is that only one stair, to the right of the entrance, leads to the second floor. A heavily turned newel post and turned balusters support an oval profile handrail which curves to the second floor. The main room is fitted with blackboards due to the later use as a school. Two square wood piers support the second floor. The small room left of the entrance is a later alteration.

The second floor is divided in the same manner with no unusual features.

## 8. Significance

Period prehistoric 1400–1499 1500–1599 1600–1699 1700–1799X 1800–1899 1900–	Areas of Significance—C — archeology-prehistoric — archeology-historic — agriculture — X architecture — art — commerce — communications		iandscape architectur iaw iterature initeratury initerature initery initerature initery initer	re religion science scuipture _X sociai/ humanitarian theater transportation other (specify)
Specific dates	c 1860–1872	Builder/Architect	nknown	

#### Statement of Significance (in one paragraph)

Applicable Criteria: A, C Criteria Exceptions: n/a

Level of Significance for Evaluation: local

#### SIGNIFICANCE SUMMARY:

The Academy Grove Historic District is significant for its architecture, comprising two well-preserved frame public buildings showing the influence of the Italianate style, a style rarely used in rural Somerset County. Notable features of both buildings include bracketed cornices and paneled corner pilasters. In addition, the District is significant for its association with the development of public education and civic organizations in the county during the third quarter of the 19th century. The Fairmount Academy is the best-preserved survivor of the county's earliest efforts to create a public educational system. The c. 1872 Knights of Pythias Hall is the only known structure in the county erected to serve as a meeting place for that organization; it is also significantly associated with education, having provided additional classroom space for the Academy as early as 1883.

OMB No. 1024-0018 Exp. 10-31-84

## United States Department of the Interior National Park Service

### National Register of Historic Places Inventory—Nomination Form

Continuation sheet Academy Grove Historic District
Somerset County, Maryland Item number

For NPS use only
rectnived
date emitered

Page

3

#### HISTORY AND SUPPORT:

Local tradition has held to an 1839 date of establishment for a school house on Potato Neck. The earliest documented reference is found in the will of Lazarus Maddox, which was proved on March 26, 1841,

It is my will that I now establish and confirm the following to be the line between my home farm above described and my other lands hereafter mentioned - commencing at the northwest corner of my field adjoining Edward T. Hall's Store on the north side of the County road in Potato Neck, from thence running with a straight line to a marked pine tree standing near the School House down the neck on the same side of the County road aforesaid."1

This marked pine and school house are referred to in an 1848 plat of a 19 3/8 acre parcel of Daniel Ballard's land, known as "School House Ridge."2 With these two firm references, it appears that a school was located on this site as early as 1839. However, a proper deed had not been executed for the school house ground. In 1867, Daniel Emery Ballard and Rosa Ballard granted to William Muir and others, "one and one half acres of land more or less to have and to hold the same in and for the use and purposes of a School House or Academy for the Education of Youth."3

Despite an uncertain date of construction for the extant academy building, it seems most probable that the trustees wanted a binding deed that would insure ownership of a new academy. A pre-1867 construction date is further strengthened by the fact that the Somerset County Board of Education Minutes begin in 1867, and no mention is made of erecting an academy in the Potato Neck District. The name "Fairmount Academy" was evidently assigned to the building around the time of its construction, for early Board of Education references mention Fairmount Academy specifically. For instance, it was ordered by the Board on April 17, 1867, that, "The Treasurer pay to the teacher of Fairmount Academy as Librarian the sum of twenty dollars provided by Chapter 7, Section 1 of the Public School Law."4

The next building project at "Academy Grove" involved the construction of the Knights of Pythias Hall, c. 1872. The Society of Knights of Pythias, was founded in 1864 by Henry Rathbone (1839-1889) in Washington, D.C. Fairmount Lodge No. 77 was established on May 5, 1872. Due to the close similarity in architectural details between the Fairmount Academy and the Knights of Pythias Hall, it is thought the structure was assembled not long after the Fairmount Lodge's inception. The first reference to the building is found in the Board of Education minute book of August 14, 1883, when a bill was submitted to the

4

# **United States Department of the Interior National Park Service**

# National Register of Historic Places Inventory—Nomination Form

Academy Grove Historic District

Continuation sheet Somerset County, Maryland Item number

For NPS use only received date entered

Page

8 and 10

#### HISTORY AND SUPPORT (continued)

Board for a \$60.00 rental of the Knights of Pythias Hall at Fairmount.<sup>6</sup> The Fairmount Chapter of Knights of Pythias dissolved in 1911, but the building was still used for additional classroom space.

In 1888, the Fairmount Academy Building was graced with a school bell ordered through the McShane Bell Foundry, McShane Company of Baltimore, MD. The notice of purchase was signed by John Hall, William E. Muir, A. Whittington, John Ford and L.H. Miles. From the late 19th century until 1927, all twelve grades were offered by an academy staff of five: one principal and four teachers. Beginning in 1927, the grades were cut back to one through seven, and from 1944 to 1969 only the first six grades were taught. 8

In 1972, a decision to auction off all unused school buildings was made by the Somerset County Commissioners. This action galvanized a group of local residents to establish the Fairmount Academy Historical Association. This group holds a lease on the property, as long as they maintain the buildings.

#### Footnotes

### VERBAL BOUNDARY DESCRIPTION AND JUSTIFICATION

The nominated property,  $1\frac{1}{2}$  acres, comprises the single lot upon which the buildings stand, and represents the historic transferred setting around these two structures. It comprises the property transferred in 1867 from Thomas E. Ballard to the trustees of Fairmount Academy, and is traditionally known as "Academy Grove," a reference to the mature trees which enhance the setting of the buildings. Boundaries are depicted on the attached map.

Somerset County Will Book, JP 5/117, March 26, 1841.

<sup>&</sup>lt;sup>2</sup>Survey of Daniel Ballard Land, August 12, 1848.

<sup>&</sup>lt;sup>3</sup>Somerset County Deed Book 4/6/1867.

Somerset County Board of Education Minutes, April 17, 1867.

Information for Knights of Pythias supplied by Viola Landen, a Fairmount resident.

<sup>&</sup>lt;sup>6</sup>Board of Education Minutes, August 14, 1883.

Notice for purchase of bell on file at Fairmount Academy, 1888.

<sup>&</sup>lt;sup>8</sup>Chesapeake Bay Magazine, "Fairmount Academy, 1839-1969", Michael C. Wooten, March 1980.

# 9. Major Bibliographical References

S-115

See Continuation Sheet No. 5

10. Geo	graphical Data		
	ated property 1.5 acres		
Quadr <mark>angle name</mark> UMT References	Marion, Maryland		Quadrangle scale 1:24,000
	0   8   0   4   2   1   6   9   5   0	. B	iting Northing
	, wording	D	wortning
		F L L	<del></del>
علا ليا		нц Ц	
erbal boundary	description and justification		
See Cont	inuation Sheet No. 4		
.ist all states ar tate n/a	nd counties for properties overla		_
tate 117 ti	code	county	code
tate	code	county	code
1. Forr	n Prepared By		
ame/title	Paul Touart - Architect	ural Historian	
rganization	Somerset County Historic	cal Trust date	October 27, 1983
reet & number	424 North Somerset Avenu	ue <b>teleph</b> o	one Home 301-651-1094
ty or town	Princess Anne	state	Maryland 21853
2. Stat	e Historic Prese	rvation Of	icer Certification
	ificance of this property within the s		
		X iocal	
55), I hereby nomi	State Historic Preservation Officer for nate this property for inclusion in the iteria and procedures set forth by the	e National Register and c	reservation Act of 1966 (Public Law 89– ertify that it has been evaluated and Recreation Service.
tate Historic Pres	ervation Officer signature	Mith	- 3-20-84
le	STATE HISTORIC PRESERVA	rion officer	date
For HCRS use on	•	· · · · · · · · · · · · · · · · · · ·	
I hereby certi	fy that this property is included in th	e National Register	
Keeper of the Nat	ional Pagietar		date
•	inia: ueðistei		doko
Attest: Chief of Registrat	los		date

OMB No. 1024-0018 Exp. 10-31-84

S-115

# United States Department of the Interior National Park Service

## National Register of Historic Places Inventory—Nomination Form

Academy Grove Historic District
Continuation sheet Somerset County, Maryland Item number

For NPS use only received date entered

Page

9

### MAJOR BIBLIOGRAPHICAL REFERENCES:

Chesapeake Bay Magazine, "Fairmount Academy, 1839-1969", Michael C. Wooten, March 1980.

Board of Education Minute Books - 1867 - 1883, Housed at Board of Education, Princess Anne, Maryland.


Landen, Viola, Personal papers and history of Fairmount Academy and Knights of Pythias.


Miscellaneous records on file at Fairmount Academy - Notice for purchase of Bell, 1888.

Somerset County Deed Books.

Somerset County Wills.

Survey of Daniel Ballard Land, August 12, 1848, Supplied by L. Q. Powell.







Fairmount Academy Upper Fairmount CVD 11/90 5-115

happe and the



Fairmount Academy Upper Fairmount CNP WAS 5-115



Fairmount Academy upper Fairmount OUN MOO 5-115




Fairmount Academy upper Fairmount CNP 11/00

5-115



Fairmount Academy
upper Fairmount
CVA 11/90
5-115



Fairmount Academy upper Fairmount CND 11/90 5-115



Somekset -108
FAIRMOUNT ACADEMY
S-115



ACADEMY GROVE H.D., SOMERSET COUNTY, MARYLAND

"Fairmount Academy S-115
near Upper Fairmount
southeast elevation
Photographer-Paul Touart
September 1983

NEG AT MHT, 21 STATE CIRCLE, ANNAPOHS, MD 21401



Comercial - 1018
FAIRMOUNT ACADEMY

5-115



Somerset - 108
FRIRMOUNT ACHDENY
S-115



Somerset - 108
Fairmount Academy
S-115



### NOALTERNY GRAME A.D., SOMERSLY COUNTY, MAKYLAND

Fairmount Academy S-115
near Upper Fairmount
staircase
Photographer-Paul Touart
September 1983

NEG. AT MIT, 21 STATE CIRCUT, ANNATELIS, MD 21401